

Klickitat County Port District No. 1
ADDENDUM NO. 1

2014-04 – Bingen Point Flooring
April 9, 2014

Q1. Will the walls be painted before or after the cove base is installed?

A1. Before. Port personnel will paint the walls after any existing cove base is removed and before new cove base is installed. Installer should plan to remove any existing cove base immediately upon the start of work to permit time for any new paint to dry.

Q2. How should the transitions between each room be addressed?

A2. Installer shall provide and install Roppe “Rolling Traffic” transitions appropriate for one-quarter inch (1/4”) high carpet and of the same cove base color in all areas where the linoleum shall abut existing carpet (2 doorways). Installer shall provide and install Roppe “Reducer Strip” transitions appropriate for the thickness of the linoleum and of the same cove base color in all other areas that do not abut other flooring (3 doorways).

Q3. Can the response to the RFQ be sent via fax or e-mail?

A3. Responses to the RFQ may be sent via fax to 509-493-4257 or via e-mail (in Adobe Portable Document Format [PDF]) to port@portofklickitat.com, provided that a signed paper copy of the proposal is mailed to the Port the same day. The Port is not responsible for errors or failures in transmission including communication failures, SPAM filters, etc.