

**Klickitat County Port District No. 1**  
**ADDENDUM NO. 1**

2015-06 – RAMCo Site Cap  
August 31, 2015

**THIS ADDENDUM MAY CHANGE THE TERMS AND CONDITIONS OF THE CONTRACT**  
**\*\*\* REMEMBER TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM \*\*\***

**Q1. Does the contractor have to maintain or improve the access road?**

A1. No. However, the access road passes through private property. As a result, the contractor should keep all trucks and equipment in the road until it crosses under the BPA power lines to the east and should take reasonable care to maintain the road in its existing condition.

**Q2. Where are the property boundaries?**

A2. The property line along the northeast edge of the north borrow area and the fill area and common with the U.S. Army Corps of Engineer's Spearfish Lake is marked by a barbed-wire fence. The property line along the northwest edge of the north and southwest borrow areas will be staked by Tenneson Engineering prior to the start of construction.

**Q3. Is the stockpile of native soil along the north side of the access road available for use?**

A3. No. This stockpile is privately owned, located on private property, and is not available for use by the contractor

**Q4. Are slopes for drainage required in the southwest borrow area?**

A4. No, provided there is a reasonable expectation of infiltration into, and migration through, any remaining soil. Exposed horizontal rock surfaces that may be impervious and create conditions reasonably expected to retain perched water should have a sloped cover. Depressions and shallow pits in the southwest borrow area may be allowed to remain by the contractor, provided that they do not present a substantial danger to persons.

**Q5. Will third-party trucks delivering concrete fill material be able to back into the fill area?**

A5. No. These trucks will utilize a side dump trailer and must be able to drive into the site, dump, and turn around to exit. The contractor must insure that the preliminary and on-going work accommodates this method of operation.

**Q6. When will concrete fill material be delivered?**

A6. On Thursday of each week during the period concrete fill is to be delivered, the contractor will receive a schedule of expected delivery periods for the following week. However, as with all construction schedules, unexpected circumstances may result in last-minute alterations.

**Q7. Is prevailing wage required?**

A7. Yes, unless the contractor meets the requirements to be considered an "Independent Contractor" as described in Section 39.12.100 of the Revised Code of Washington (RCW).