

**Klickitat County Port District No. 1**  
**ADDENDUM NO. 1**

2022-02 – BPT Irrigation-Drainage-Fill Project  
April 25, 2022

**THIS ADDENDUM MAY CHANGE THE TERMS AND CONDITIONS OF THE CONTRACT**  
**\*\*\* REMEMBER TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM \*\*\***

**GENERAL:**

1. Marina Drywell Repair (Additive Item #1) – The Provider is to provide a 5 oz/SY, woven, silt film, geotextile fabric between the subgrade and the proposed base aggregate in the ~15' x 18' asphalt repair area adjacent to the drywell. Acceptable products include GEO 250W (GeoCHEM Inc), S250 (ACF Environmental), US 250 (US Fabrics), or approved equal.
  
2. Lot 9 Boundary Fill (Additive Item #2) - The Port has cleared some of the vegetation and installed silt fence on a portion of the west and south edges of Lot 9. **Not ALL of the clearing and grubbing has been completed.** The Port will install silt fence at the wetland buffer boundary once the Provider has cleared all remaining vegetation, stumps and oversize boulders from the fill area. The Provider is to familiarize themselves with the Work completed by the Port and include any remaining Work in their Quote.

**\*\*\* The brief description of changes is not comprehensive and the Provider is responsible to review the Contract Document and Plans for all changes to the Work \*\*\***