

**Klickitat County Port District No. 1**  
**ADDENDUM NO. 1**

2022-04 – DIP Well #2 Disinfection and Improvements Project  
October 28, 2022

**THIS ADDENDUM MAY CHANGE THE TERMS AND CONDITIONS OF THE CONTRACT**  
**\*\*\* REMEMBER TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM \*\*\***

**GENERAL:**

1. Any vegetation that must be cleared to provide construction access may be neatly piled and left on-site as directed by the Port. Do not pile under overhead utilities.

**PLANS:**

2. SITE PLAN (C-102) – Replace with revised SITE PLAN sheet. The Chlorine Injection Assembly (Base Bid) has been relocated closer to the Pump Building and Additive #4 will include extending the second 1-1/2" PVC sleeve to the Flowmeter Vault from its termination at the Chlorine Injection Assembly vault.
3. BUILDING MODIFICATIONS (C-103) – Replace with revised BUILDING MODIFICATIONS sheet. The chlorine tubing is to be placed inside a 1-1/2" PVC Sch 40 sleeve attached to the interior of the Pump Building walls. Provide a 2-foot gap where the tubing exits through the foundation wall to allow access.

***\*\*\* The brief description of changes is not comprehensive and the Provider is responsible to review the Contract Document and Plans for all changes to the Work \*\*\****